

**Killargue Graves Committee**

**Proposed Works at Killargue NEW Cemetery, Killargue, County Leitrim**

**Schedule of Prices**

Ref.	Description	Unit	Cost (€)
1.	Breakup Existing Concrete Paving and reuse as fill to new Roads	Item	
2	Lay New Concrete Surface, Including Terram GeoGrid, Clause 804 Base, 75mm C20/25 Concrete, One Layer of A142 Mesh, Brush Surface Finish. Minimum 1.2m Wide. All as indicated on the Drawing. For Path Repair refer to item 1 above	51m @	
3	Lay New Concrete Surface, Including Terram GeoGrid, Clause 804 Base, 100mm C20/25 Concrete, One Layer of A142 Mesh, Brush Surface Finish. Minimum 3m Wide. All as indicated on the Drawing. For Drive repair refer to item 1 above	77m @	
4	Provide - 150mm Diameter Twin Wall High Density Corripipe, Bed, Surround and Backfill to Ground Level with Clause 804	42m @	
5	Provide - 225mm Diameter Twin Wall High Density Corripipe, Bed, Surround and Backfill Pipe to Ground level with Clause 804	131m @	
6	Provide - 300mm Diameter Twin Wall High Density Corripipe, Bed, Surround with Drainage Stone and Backfill to Ground Level with Clause 804	23m @	
7	Provide Twin Wall High Density Corripipe Joints & Bends	Item	
8	Provide Handrails, supports fittings & fixing in place, all to part M of Building Regs (copy of detail attached)	30m	
9	Provide 2 no. Weather Proof Bench Seats to Client Specification and fix inplace at locations as directed	Item	
10	Allow for Re-Opening Existing Open Drain - 1.5m Wide x 1.5m Deep. All To Falls	120m @	
11	Provide Boulder and Stone to Drain as shown on Bends & Surround to 300mm Diameter Corripipe at End of Existing Open Drain and SOAKAWAY - Approx Qty 20 m Cu.	Item	
12	Trim Existing Deciduous Hedgerow over complete length	75m	
13	Allow for Contractor's Own Preliminaries; Insurances, Supervision, Health and Safety Etc. Contingences Sum €500	Item	
14	<b>Nett Total</b>		
15	Add VAT at 13.5%		
16	<b>TOTAL</b>		