

Killargue Graves Committee

Proposed Drainage Works at Killargue NEW Cemetery, Killargue, Co. Leitrim

Schedule of Prices

Ref.	Description	Unit	Cost (€)
1.	Breakup Existing Concrete Paving and reuse as fill on new roads & footpaths	Item	
2.	Lay New Concrete Surface, Including Terram GeoGrid, Clause 804 Base, 100mm C20/25 Concrete, One Layer of A142 Mesh and Steel Trowel Surface Finish. Minimum 3m Wide. All as indicated on the Drawing.	54m	
3	Lay New Concrete Surface, Including Terram GeoGrid, Clause 804 Base, 75mm C20/25 Concrete, One Layer of A142 Mesh and Steel Trowel Surface Finish. Minimum 1.2m Wide. All as indicated on the Drawing.	50m	
4	Provide Twin Wall High Density Corripipe, Bed, Surround and Backfill Pipe with Clause 804 Harcore - 150mm Diameter	40m	
5	Provide Twin Wall High Density Corripipe, Bed, Surround and Backfill Pipe with Clause 804 Harcore - 300mm Diameter	66m	
6	Provide Twin Wall High Density Corripipe, Bed, Surround and Backfill Pipe with Clause 804 Harcore - 600mm Diameter	23m	
5.	Provide Twin Wall High Density Corripipe Joints & Bends as required	Item	
6.	Handrail, supports, fittings & fixing in place, all to part M (copy attached)	50m	
7.	Allow for Locating and Clearing Where Possible the Original Drainpipe	Item	
8.	Allow for Re-Opening Existing Open Drain - 1.5m Wide x 1.5m Deep. All To Falls	120m	
9	Provide Boulder and Stone to Drains as shown on Soakaway (20m ³), Bends & surround to 600 Diam Corripipe at End of Existing Open Drain	Item	
10	Trim Existing Deciduous Hedgerow	Item	
11	Allow for Contractor's Own Preliminaries; Insurances, Supervision, Health and Safety Etc.	Item	
12	Nett Total		
13	Add VAT at 13.5%		
14	TOTAL		